


"Doctor Faustus"
Video Control Layout

Director: Leon Ingulsrud
Digital Media Artist & Technical Director: Kevin Abbott
Asst. Digital Media Artist: Micah Stieglitz
Asst. Digital Media Technical Director: Benjamin G. Stickle
Drawn by: Benjamin G. Stickle

No Scale
Revision: 3
02-20-2007
REVISED: 03-23-07 -BG-



All computer stations and Vicon Datastation to have UPS units installed on incoming power.

At least 8 independent circuits are needed:
3: Projectors and Signal Extenders (Two of these circuits will come from the wings for the rear projectors, the stereo pair will have two non-dim circuits from the stage lighting rig.)
2: Computer Stations
Vicon Datastation
1: Audio Console and Wireless receivers

All equipment to be secured with security loops and locks.
Cameras to be mounted to the trussing over the trap pit.
All control gear to be placed in the orchestra pit as per the director, technical director, and media technical director.
All control and signal cables to terminate in the orchestra pit.

Backup Machines

- Baal
Xeon 233
7300 LE
Vicon IQ Backup
- Diablo
QX6700 Quad
7800GT
Motion Builder Backup
- MacBook Pro
Modul8 Backup

